

COCHIN PORT TRUST

www.tenderwizard.com/CPT



Tender No: T6/T-1931/2020-C Date: 11-11-2020- (PRICE BID)

Name of Work: "Casting Concrete sinkers for Navigational Channel Buoys"

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
	T6/T-1931/2020 -C						
1	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete using Thermo Mechanically Treated bars including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and direction of Engineer-in-charge.	1000.00	Kg	113.48	Rupees One Hundred Thirteen and Forty Eight Paise Only	113480.00	Rupees One Lakh Thirteen Thousand Four Hundred Eighty Only
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns. as per detailed specifications, drawing and directions of Engineer-in-Charge.	95.00	M2	997.13	Rupees Nine Hundred Ninety Seven and Thirteen Paise Only	94727.35	Rupees Ninety Four Thousand Seven Hundred Twenty Seven and Thirty Five Paise Only
3	Providing and laying in position reinforced cement concrete of grade 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size) for all work up to plinth level excluding the cost of centering, shuttering, and reinforcement but including cost of all labour, equipments, tools, levelling, finishing, curing etc, complete as per detailed specifications and direction of Engineer-in-charge	23.00	M3	12647.23	Rupees Twelve Thousand Six Hundred Forty Seven and Twenty Three Paise Only	290886.29	Rupees Two Lakh Ninety Thousand Eight Hundred Eighty Six and Twenty Nine Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
4	Finishing with EPOxy paint (two or more coats) at all locations prepared and applied as per manufacturers specification including appropriate priming coat, preparation of surface etc. complete on concrete work as per the direction of the Engineer in charge	110.00	M2	257.40	Rupees Two Hundred Fifty Seven and Forty Paise Only	28314.00	Rupees Twenty Eight Thousand Three Hundred Fourteen Only
	Total					527407.64	Rupees Five Lakh Twenty

BIDDERS QUOTING AREA

				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail 5.Wrongful entry of quotes shall entail disqualifications besides other actions as the Employee deem fit.				527407.64			

" This is a Electronic Submission No Need of Signature"