

COCHIN PORT AUTHORITY					
www.cochinport.gov.in					
Tender No.:					
Name of work: Construction of pump house for permanent pumping facility at OTB for yearly hydro testing of IOCL dock lines for IOCL at NTB, Cochin Port					
<u>SCHEDULE: - SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT</u>					
Sl. No	Description of items of work	Approximate Quantity/ No	Unit	Rates in Rs.	Amount Rs
1	Providing and laying reinforced cement concrete of M 40 grade for precast piles 400 mm square and 22.0 m long excluding reinforcement but including cost of materials and labour, admixtures, shuttering, levelling, vibrating, providing toggle holes, curing, sampling and testing, stacking of piles etc. complete as per drawing etc.	21.20	m ³		
2	Providing and fixing reinforcement using TMT/HYSD/CRS bars for the RCC work under item No.1 above including cost of all materials, labour, transporting to site, cutting, welding, bending, straightening and tying and fixing in position, sampling and testing, providing cover blocks etc. complete as per drawings etc.	4.90	T		
3	Removing the precast RCC piles 400mm square and 22 m long already cast and stacked from the stacking / casting yard, transporting to the pitching location and pitching in position as per drawing etc.	6.00	E		
4	Driving the piles pitched under item No. 3 above from the pitched position to the founding level as per drawings etc. Payment will be made only for the actual depth of driving from the pitched level to the founding level.	78.00	m		
5	Providing and laying reinforced cement concrete of M 40 grade for pile caps and capping beams excluding reinforcement but including cost of materials and labour, admixtures, shuttering, levelling, vibrating, providing toggle holes, curing, sampling and testing, etc. complete as per drawing .	4.90	m ³		
6	Providing and laying reinforced cement concrete of M 30 grade for deck slab excluding reinforcement but including cost of materials and labour, admixtures, shuttering, levelling, vibrating, providing toggle holes, curing, sampling and testing, etc. complete as per drawing.	8.30	m ³		
7	Providing and fixing reinforcement using TMT/HYSD/CRS bars for the RCC work under item No.5 & 6 above including cost of all materials, labour, transporting to site, cutting, welding, bending, straightening and tying and fixing in position, sampling and testing, providing cover blocks etc. complete as per drawings etc.	2.50	T		

Note : Rates shall be excluding GST