

COCHIN PORT AUTHORITY

www.tenderwizard.com/CPT

Tender No: T6/Q-14/2024-C Date: 21-11-2024- (PRICE BID)

Name of Work:- Providing and fixing concrete posts in Cochin Port land at eastern side of Container road, Mulavukadu

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil including cost of all labor, tools, equipments etc. complete as per detailed specifications and directions of the Engineer-in-charge.	16	One Cubic Metre	247.14	Rupees Two Hundred Forty Seven and Fourteen Paise Only	3954.24	Rupees Three Thousand Nine Hundred Fifty Four and Twenty Four Paise Only
2	R.C.C. Standards post/ struts/rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarsesand : 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6mm bar nibs wherever required as per direction of Engineer-incharge (cost of earth works in excavation, concrete works in foundation to be paid separately) including reinforcement, shuttering, plastering etc. complete as per detailed specificatons and directions of the Engineer-in-charge	3.00	One Cubic Metre	36360.23	Rupees Thirty Six Thousand Three Hundred Sixty and Twenty Three Paise Only	109080.69	Rupees One Lakh Nine Thousand Eighty and Sixty Nine Paise Only
3	Providing and laying in position cement concrete of specified grade sexcluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size) icluding cost of all labour, materials, tools etc. complete as per detailed specifications and directions of Engineer-in-charge.	16.00	One Cubic Metre	8506.37	Rupees Eight Thousand Five Hundred Six and Thirty Seven Paise Only	136101.92	Rupees One Lakh Thirty Six Thousand One Hundred One and Ninety Two Paise Only
	Total					249136.85	

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
BIDDERS QUOTING AREA							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail			249136.85			
" This is a Electronic Submission No Need of Signature"							