

COCHIN PORT AUTHORITY

www.tenderwizard.com/CPT

Tender No: T6/Q-01/2025-C Date:- 02-01-2025- (PRICE BID)

Name of Work:- Demolishing the damaged sunshade slab and reconstructing with steel structure at Kendriya Vidyalaya Port Trust

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Dismantling R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 50m, stacking serviceable and unserviceable material separately including cutting reinforcement bars, cost of all labour, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-Charge.	18	One Cubic Metre	3444.76	Rupees Three Thousand Four Hundred Forty Four and Seventy Six Paise Only	62005.68	Rupees Sixty Two Thousand Five and Sixty Eight Paise Only
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all labour, materials, tools, equipments, scaffolding, curing etc. complete as per detailed specification and directions of the Engineer-in-charge.	7.50	One Cubic Metre	10315.73	Rupees Ten Thousand Three Hundred Fifteen and Seventy Three Paise Only	77367.98	Rupees Seventy Seven Thousand Three Hundred Sixty Seven and Ninety Seven Paise Only
3	Plastering with cement mortar 1:4 (1 cement: 4 fine sand) 12 mm thick including finishing, curing, all labour, materials, scaffolding, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	73.00	One Square Metre	375.30	Rupees Three Hundred Seventy Five and Thirty Paise Only	27396.90	Rupees Twenty Seven Thousand Three Hundred Ninety Six and Ninety Paise Only
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer including cost of all labour, materials, tools, scaffolding etc. complete as per detailed specifications and directions of Engineer-in-Charge.	73.00	One Square Metre	81.54	Rupees Eighty One and Fifty Four Paise Only	5952.42	Rupees Five Thousand Nine Hundred Fifty Two and Forty Two Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
5	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coats applied at 1.67 ltr/10sqm over and including priming coat of exterior paint applied @ 2.20Kg/10Sqm) including cost of all labour, materials, scaffolding, tools, etc. complete as per detailed specifications and directions of Engineer-in-Charge.	73.00	One Square Metre	223.83	Rupees Two Hundred Twenty Three and Eighty Three Paise Only	16339.59	Rupees Sixteen Thousand Three Hundred Thirty Nine and Fifty Nine Paise Only
6	Structural steel work welded in built up sections, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge all complete.	1005.00	One Kilogram	138.28	Rupees One Hundred Thirty Eight and Twenty Eight Paise Only	138971.40	Rupees One Lakh Thirty Eight Thousand Nine Hundred Seventy One and Forty Paise Only
7	Providing roofing with troughed prepainted galvalume sheets, 0.50mm thick over purlins already fixed in position using respert grey /xylam coated anticorrosive fasteners like self drilling screws with EPDM/ Neopreme washers including cost of all materials and labour, scaffolding all lifts etc. as per the directions of Engineer-in-Charge	77.00	One Square Metre	798.1	Rupees Seven Hundred Ninety Eight and Ten Paise Only	61453.70	Rupees Sixty One Thousand Four Hundred Fifty Three and Seventy Paise Only
	Total					389487.67	Rupees Three Lakh Eighty Nine Thousand Four Hundred Eighty Seven and Sixty Six Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
BIDDERS QUOTING AREA							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail			389487.67			
" This is a Electronic Submission No Need of Signature"							