

COCHIN PORT AUTHORITYwww.tenderwizard.com/CPT

Tender No: T6/T-2045/2025 -C Date: 30/01/2025 (PRICE BID)

Name of Work: "RENOVATION OF QUARTER NO. NVII/ 04

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead for thickness of tiles 10 mm to 25 mm including cost of all labour, tools, equipment etc. complete as per detailed specifications and directions of the Engineer-in-charge.	175.00	One Square Metre	74.54	Rupees Seventy Four and Fifty Four Paise Only	13045.09	Rupees Thirteen Thousand Forty Five and Eight Paise Only
2	Dismantling W.C. Pan/ Wash basin of all sizes including disposal of dismantled materials i/c malba including cost of all labour, tools, equipment etc. complete as per detailed specifications and directions of the Engineer-in-charge.	7.00	Each	130.47	Rupees One Hundred Thirty and Forty Six Paise Only	913.27	Rupees Nine Hundred Thirteen and Twenty Seven Paise Only
3	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead including cost of all labour, tools, equipment etc. complete as per detailed specifications and directions of the Engineer-in-charge.	75.00	One Square Metre	53.00	Rupees Fifty Three Only	3975.19	Rupees Three Thousand Nine Hundred Seventy Five and Nineteen Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Department al rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
4	Plastering wih cement mortar 1:4 (1 cement: 4 fine sand) 12 mm thick including finishing, curing, all labour, materials, scaffolding, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	20.00	One Square Metre	362.66	Rupees Three Hundred Sixty Two and Sixty Five Paise Only	7253.20	Rupees Seven Thousand Two Hundred Fifty Three and Nineteen Paise Only
5	Providing and laying vitrified Floor/ wall tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including filling the joints with epoxy of matching colour etc., complete. Size of Tile 800x800 mm or suitable nearest size available in the market. including curing, cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.(Material cost not less than Rs.1318/M2)	234.00	One Square Metre	2390.14	Rupees Two Thousand Three Hundred Ninety and Fourteen Paise Only	559293.61	Rupees Five Lakh Fifty Nine Thousand Two Hundred Ninety Three and Sixty One Paise Only
6	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing including curing, cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	234.00	One Square Metre	260.73	Rupees Two Hundred Sixty and Seventy Three Paise Only	61011.25	Rupees Sixty One Thousand Eleven and Twenty Four Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc for 25 mm nominal outer dia Pipes including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	12.00	One Metre	763.71	Rupees Seven Hundred Sixty Three and Seventy One Paise Only	9164.55	Rupees Nine Thousand One Hundred Sixty Four and Fifty Five Paise Only
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc for 32 mm nominal outer dia Pipes including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	12.00	One Metre	922.99	Rupees Nine Hundred Twenty Two and Ninety Nine Paise Only	11075.90	Rupees Eleven Thousand Seventy Five and Ninety Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
9	Providing and fixing white vitreous china pedestal type water closet (European type) with white solid plastic seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required of Cera or approved equivalent make including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	4.00	Each	9085.18	Rupees Nine Thousand Eighty Five and Eighteen Paise Only	36340.73	Rupees Thirty Six Thousand Three Hundred Forty and Seventy Two Paise Only
10	Supply and Fixing Concealed Divertor of CERA Model F4010101 or approved equivalent make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge. Hindware or equivalent ,(material cost not less than Rs. 3615 each)	4.00	Each	4355.74	Rupees Four Thousand Three Hundred Fifty Five and Seventy Four Paise Only	17422.96	Rupees Seventeen Thousand Four Hundred Twenty Two and Ninety Six Paise Only
11	Supply and Fixing Shower Divertor Exposed Part of CERA-Model: F2008701 or approved equivalent make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge. (material cost not less than Rs.1660/-each)	4.00	Each	2062.52	Rupees Two Thousand Sixty Two and Fifty Two Paise Only	8250.08	Rupees Eight Thousand Two Hundred Fifty and Eight Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
12	Supply and Fixing Spout Brand of CERA Model-F1019661 or approved equivalent make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge. (material cost not less than Rs. 1320/- each)	4.00	Each	1663.70	Rupees One Thousand Six Hundred Sixty Three and Seventy Paise Only	6654.80	Rupees Six Thousand Six Hundred Fifty Four and Eighty Paise Only
13	Supply and Fixing Over Head Shower of CERA Model- F7010111SS, 150x150mm or approved equivalent make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge. (material cost not less than Rs.2085/-each)	4.00	Each	2561.05	Rupees Two Thousand Five Hundred Sixty One and Five Paise Only	10244.20	Rupees Ten Thousand Two Hundred Forty Four and Twenty Paise Only
14	Supply and Fixing Over Head Shower Arm Brand of CERA Model- F7040106 or approved equivalent make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.(material cost not less than Rs.1490/-each)	4.00	Nos	1863.11	Rupees One Thousand Eight Hundred Sixty Three and Eleven Paise Only	7452.44	Rupees Seven Thousand Four Hundred Fifty Two and Forty Four Paise Only
15	Providing and fixing 15mm nominal bore C.P. brass angle valve for Wash basin, Flush tank and Health faucet of approved quality conforming to IS:8931 532.00 including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	12.00	Nos	723.01	Rupees Seven Hundred Twenty Three Only	8676.11	Rupees Eight Thousand Six Hundred Seventy Six and Eleven Paise Only
16	Supplying & Fixing Toilet fittings Health faucet of CERA, Model F8030105AB or approved equivalent make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.(material cost not less than Rs.995/-each)	4.00	Each	1282.48	Rupees One Thousand Two Hundred Eighty Two and Forty Eight Paise Only	5129.92	Rupees Five Thousand One Hundred Twenty Nine and Ninety Two Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Department al rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
17	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved brand, quality and colour, weighing not less than 88 gms including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	5.00	Nos	310.13	Rupees Three Hundred Ten and Thirteen Paise Only	1550.66	Rupees One Thousand Five Hundred Fifty and Sixty Six Paise Only
18	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms. including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	4.00	Each	177.35	Rupees One Hundred Seventy Seven and Thirty Five Paise Only	709.42	Rupees Seven Hundred Nine and Forty One Paise Only
19	Providing and fixing PTMT shelf 440 mm long, 124 mm width and 36mm height of approved quality and colour, weighing not less than 300 gms. including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	4.00	Nos	872.91	Rupees Eight Hundred Seventy Two and Ninety One Paise Only	3491.65	Rupees Three Thousand Four Hundred Ninety One and Sixty Four Paise Only
20	Providing 300mm dia (class 2) Semicircular PVC eaves gutter with M.S. brackets 50x6mm about 1m c/c including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	20.00	One Metre	911.10	Rupees Nine Hundred Eleven and Ten Paise Only	18222.00	Rupees Eighteen Thousand Two Hundred Twenty Two Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Department al rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
21	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, with Single socketed pipes of 110 mm diametre including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	28.00	One Metre	414.58	Rupees Four Hundred Fourteen and Fifty Eight Paise Only	11608.24	Rupees Eleven Thousand Six Hundred Eight and Twenty Four Paise Only
22	Providing and fixing PTMT grating of approved quality and colour Rectangular type with openable circular lid 150 mm nominal size square 100 mm diameter of the inner hinged round grating including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	4.00	Nos	229.68	Rupees Two Hundred Twenty Nine and Sixty Seven Paise Only	918.71	Rupees Nine Hundred Eighteen and Seventy One Paise Only
23	Supplying, Laying and jointing PVC pipe (class5) with ISI mark including all specials for water supply line. 25 mm dia of approved make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge. including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	25.00	One Metre	79.00	Rupees Seventy Nine Only	1975.00	Rupees One Thousand Nine Hundred Seventy Five Only
24	Supplying, Laying and jointing PVC pipe (class5) with ISI mark including all specials for water supply line. 32 mm dia of approved make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	50.00	One Metre	97.40	Rupees Ninety Seven and Forty Paise Only	4870.00	Rupees Four Thousand Eight Hundred Seventy Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
25	Supplying, Laying and jointing PVC pipe (class5) with ISI mark including all specials for water supply line. 40 mm dia of approved make including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	20.00	One Metre	122.10	Rupees One Hundred Twenty Two and Ten Paise Only	2442.00	Rupees Two Thousand Four Hundred Forty Two Only
26	Supplying and laying /fixing 63mm dia. PVC pipe (class2) of approved equivalent make buried /above ground for drainage disposal including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	40.00	One Metre	172.50	Rupees One Hundred Seventy Two and Fifty Paise Only	6900.00	Rupees Six Thousand Nine Hundred Only
27	Supplying and laying /fixing 110mm dia. PVC pipe (class2) of approved equivalent make buried /above ground for drainage disposal including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	40.00	One Metre	338.80	Rupees Three Hundred Thirty Eight and Eighty Paise Only	13552.00	Rupees Thirteen Thousand Five Hundred Fifty Two Only
28	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. including cost of all labour, tools, equipments etc. complete as per the directions of Engineer-in-charge.	20.00	One Cubic Metre	188.70	Rupees One Hundred Eighty Eight and Seventy Paise Only	3774.05	Rupees Three Thousand Seven Hundred Seventy Four and Five Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
29	Providing and fixing mosquito shuttering to windows, ventilators/ opening/ grills using powder coated aluminium section no.9948 of shell thickness of 1.5mm , SS net grade 316, including all labour and materials, SS handles 3"/2", SS hinges 3"/2", Magnet,tower bolt, spring, bush and beedings etc. including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	49.00	One Square Metre	1680.00	Rupees One Thousand Six Hundred Eighty Only	82320.00	Rupees Eighty Two Thousand Three Hundred Twenty Only
30	Providing and fixing mosquito shuttering to doors using powder coated aluminium section no.9948 of shell thickness 1.5 mm, SS net grade 316, including all labour and materials,SS handles 3"/2", SS hinges 3"/2", Magnet,tower bolt, spring, bush and beedings etc. including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	7.00	One Square Metre	2100.00	Rupees Two Thousand One Hundred Only	14700.00	Rupees Fourteen Thousand Seven Hundred Only
31	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require using White Vitreous China Flat back wash basin of size 550x 400 mm with single 15 mm C.P. brass pillar tap including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	4.00	Each	3411.80	Rupees Three Thousand Four Hundred Eleven and Eighty Paise Only	13647.21	Rupees Thirteen Thousand Six Hundred Forty Seven and Twenty Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
32	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour with Waste coupling of size 38 mm dia of 83 mm length and 77mm breadth, weighing not less than 60 gms including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	4.00	Each	161.05	Rupees One Hundred Sixty One and Four Paise Only	644.18	Rupees Six Hundred Forty Four and Eighteen Paise Only
33	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : (a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/ sqm. This layer will be allowed to air cure for 4 hours. (b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. (The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.) including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	102.00	One Square Metre	632.77	Rupees Six Hundred Thirty Two and Seventy Six Paise Only	64542.44	Rupees Sixty Four Thousand Five Hundred Forty Two and Forty Four Paise Only
34	Dismantling G.S. Sheet roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-	24.00	One Square Metre	165.67	Rupees One Hundred Sixty Five and Sixty Six Paise Only	3976.01	Rupees Three Thousand Nine Hundred Seventy Six Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
35	Providing roofing with troughed prepainted galvalume sheets, 0.50mm thick over purlins already fixed in position using respert grey /xylam coated anticorrosive fasteners like self drilling screws with EPDM/Neopreme washers including cost of all materials and labour, scaffolding all liofts etc. including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	24.00	One Square Metre	798.10	Rupees Seven Hundred Ninety Eight and Ten Paise Only	19154.40	Rupees Nineteen Thousand One Hundred Fifty Four and Forty Paise Only
36	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	300.00	One Kilogram	138.28	Rupees One Hundred Thirty Eight and Twenty Eight Paise Only	41484.70	Rupees Forty One Thousand Four Hundred Eighty Four and Sixty Nine Paise Only
37	Providing and fixing precoated galvanised steel sheet roofing accessories Flashings/ Aprons (Upto 600 mm) 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	12.00	One Metre	500.94	Rupees Five Hundred and Ninety Four Paise Only	6011.31	Rupees Six Thousand Eleven and Thirty Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
38	Providing and fixing precoated galvanised steel sheet roofing accessories, Ridges plain (500 - 600mm) 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws Ridges plain (500 - 600mm) including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	7.00	One metre	565.77	Rupees Five Hundred Sixty Five and Seventy Six Paise Only	3960.38	Rupees Three Thousand Nine Hundred Sixty and Thirty Seven Paise Only
39	Demolishing brick work in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead including cost of all labour, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	2.00	One Cubic metre	1997.65	Rupees One Thousand Nine Hundred Ninety Seven and Sixty Five Paise Only	3995.31	Rupees Three Thousand Nine Hundred Ninety Five and Thirty Paise Only
40	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. including cost of all labour, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	1110.00	One Square metre	24.80	Rupees Twenty Four and Eighty Paise Only	27530.75	Rupees Twenty Seven Thousand Five Hundred Thirty and Seventy Five Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
41	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	450.00	One Square metre	156.49	Rupees One Hundred Fifty Six and Forty Nine Paise Only	70422.06	Rupees Seventy Thousand Four Hundred Twenty Two and Five Paise Only
42	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	852.00	One Square metre	81.54	Rupees Eighty One and Fifty Four Paise Only	69474.12	Rupees Sixty Nine Thousand Four Hundred Seventy Four and Twelve Paise Only
43	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two Coats including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	940.00	One Square metre	154.79	Rupees One Hundred Fifty Four and Seventy Nine Paise Only	145506.98	Rupees One Lakh Forty Five Thousand Five Hundred Six and Ninety Seven Paise Only

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
44	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. 13.48A.1 New work (Two or more coats applied @ 1.43 litre/10 sqm. over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	280.00	One Square metre	198.69	Rupees One Hundred Ninety Eight and Sixty Nine Paise Only	55633.66	Rupees Fifty Five Thousand Six Hundred Thirty Three and Sixty Six Paise Only
45	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of Engineer-in-charge.	310.00	One Square metre	108.66	Rupees One Hundred Eight and Sixty Five Paise Only	33683.13	Rupees Thirty Three Thousand Six Hundred Eighty Three and Twelve Paise Only
46	Mirror polishing on marble work/ Granite work/ stone work where ever required to give high gloss finish including cost of all labour, materials, tools, equipments etc. complete as per the directions of Engineer-in-charge.	100.00	One Square metre	500.13	Rupees Five Hundred and Twelve Paise Only	50012.67	Rupees Fifty Thousand Twelve and Sixty Seven Paise Only
	Total					1542616.34	Rupees Fifteen Lakh Forty Two Thousand Six Hundred Sixteen
BIDDERS QUOTING AREA							

Sl.No	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	Notes : 1. The Tenderer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3. Tenderers shall also quote Above/ Below in words themselves in the last column. 4. In case of discrepancy in words and figures the quoted figure in word will prevail			1542616.34			
" This is an Electronic Submission. No Need of Signature"							