

**COCHIN PORT AUTHORITY**

[www.tenderwizard.com/CPT](http://www.tenderwizard.com/CPT)

Quotation No: T6/Q-06/2025-C - (PRICE BID)

**Name of Work:- Casting of Concrete Sinkers for Navigational Buoys**

**SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT**

Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete using Thermo Mechanically Treated bars including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and direction of Engineer-in-charge.	700	One Kilogram	113.48	<b>Rupees One Hundred Thirteen and Forty Eight Paise Only</b>	79436.00	<b>Rupees Seventy Nine Thousand Four Hundred Thirty Six Only</b>
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns. as per detailed specifications,drawing and directions of Engineer-in Charge.	70.00	One Square Metre	997.13	<b>Rupees Nine Hundred Ninety Seven and Thirteen Paise Only</b>	69799.10	<b>Rupees Sixty Nine Thousand Seven Hundred Ninety Nine and Ten Paise Only</b>
3	Providing and laying in position reinforced cement concrete of grade 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size) for all work up to plinth level excluding the cost of centering, shuttering, and reinforcement but including cost of all labour, equipments, tools, levelling, finishing, curing etc, complete as per detailed specifications and direction of Engineer-in-charge	17.00	One Cubic Metre	12647.23	<b>Rupees Twelve Thousand Six Hundred Forty Seven and Twenty Three Paise Only</b>	215002.91	<b>Rupees Two Lakh Fifteen Thousand Two and Ninety One Paise Only</b>
4	Finishing with EPOxy paint (two or more coats) at all locations prepared and applied as per manufacturers specification including appropriate priming coat, preparation of surface etc. complete on concrete work as per the direction of the Engineer in charge	80.00	One Square Metre	257.40	<b>Rupees Two Hundred Fifty Seven and Forty Paise Only</b>	20592.00	<b>Rupees Twenty Thousand Five Hundred Ninety Two Only</b>
	<b>Total</b>					<b>384830.01</b>	

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
<b>BIDDERS QUOTING AREA</b>							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	<b>Notes :</b> 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discrepancy in words and figures the quoted figure in word will prevail			384830.01			
<b>" This is a Electronic Submission No Need of Signature"</b>							