

COCHIN PORT AUTHORITY

www.tenderwizard.com/CPT

Quotation No: T6/Q-07/2025-C - (PRICE BID)

Name of Work:- REPLACING DAMAGED CEILINGS AND ROOFING SHEETS AT CISF BARRACK

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: Asbestos cement sheet including cost of all labour, tools, equipments etc. complete as per detailed specifications and direction of Engineer-in-charge.	150	One Square Metre	77.33	Rupees Seventy Seven and Thirty Three Paise Only	11599.50	Rupees Eleven Thousand Five Hundred Ninety Nine and Fifty Paise Only
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. 14.1.1 With cement mortar 1:4 (1 cement : 4 fine sand) including cost of all labour, materials tools, equipments etc. complete as per detailed specifications and direction of Engineer-in-charge..	20.00	One Square Metre	567.81	Rupees Five Hundred Sixty Seven and Eighty One Paise Only	11356.20	Rupees Eleven Thousand Three Hundred Fifty Six and Twenty Paise Only
3	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately). 12.26.1 6 mm thick Cement fiber board as per IS: 14862 including cost of all labour, materials, equipments, tools, levelling, finishing, etc, complete as per detailed specifications and direction of Engineer-in-charge	150.00	One Square Metre	996.24	Rupees Nine Hundred Ninety Six and Twenty Four Paise Only	149436.00	Rupees One Lakh Forty Nine Thousand Four Hundred Thirty Six Only
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost of all labour, materials, equipments, tools, etc. complete as per detailed specifications and direction of Engineer-in-charge	1100.00	One Kilogram	138.28	Rupees One Hundred Thirty Eight and Twenty Eight Paise Only	152108.00	Rupees One Lakh Fifty Two Thousand One Hundred Eight Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches including cost of all labour, equipments, tools, etc. complete as per detailed specifications and direction of Engineer-in-charge	150.00	One Square Metre	24.80	Rupees Twenty Four and Eighty Paise Only	3720.00	Rupees Three Thousand Seven Hundred Twenty Only
6	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface including cost of all labour, materials, equipments, tools, etc. complete as per detailed specifications and direction of Engineer-in-charge	250.00	One Square Metre	81.54	Rupees Eighty One and Fifty Four Paise Only	20385.00	Rupees Twenty Thousand Three Hundred Eighty Five Only
7	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour including cost of all labour, materials, equipments, tools, etc. complete as per detailed specifications and direction of Engineer-in-charge .	250.00	One Square Metre	154.79	Rupees One Hundred Fifty Four and Seventy Nine Paise Only	38697.50	Rupees Thirty Eight Thousand Six Hundred Ninety Seven and Fifty Paise Only
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work including cost of all labour, materials, equipments, tools, etc. complete as per detailed specifications and direction of Engineer-in-charge .	150.00	One Square Metre	108.66	Rupees One Hundred Eight and Sixty Six Paise Only	16299.00	Rupees Sixteen Thousand Two Hundred Ninety Nine Only
9	Providing and fixing ridges and hips in fibre cement reinforced by organic fibres and/or inorganic synthetic fibres roofing with suitable fixing accessories or self drilling fastener and EPDM washer etc. complete. Corrugated serrated adjustable ridges including cost of all labour, materials, equipments, tools, etc. complete as per detailed specifications and direction of Engineer-in-charge .	25.00	One Metre	589.01	Rupees Five Hundred Eighty Nine and One Paise Only	14725.25	Rupees Fourteen Thousand Seven Hundred Twenty Five and Twenty Five Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
10	Providing Asbestos Sheet or equivalent cement sheet 6mm thick corrugated sheets roofing up to any pitch and fixing with Polymer coated J, or L hooks, bolts & nuts 8mm dia. GI plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding cost of purlins, rafters and trusses) including cutting sheets to size and shape wherever required with the retrieved sheets supplied departmentally at free of cost including cost of all labour, material except roofing sheet etc. complete as per directions of the Engineer-in-charge.	60.00	One Square Metre	155.06	Rupees One Hundred Fifty Five and Six Paise Only	9303.60	Rupees Nine Thousand Three Hundred Three and Sixty Paise Only
11	Supplying good approved quality Asbestose Cement corrugated roofing sheet or equivalent roofing sheets upto any pitch.	60.00	One Square Metre	293.25	Rupees Two Hundred Ninety Three and Twenty Five	17595.00	Rupees Seventeen Thousand Five Hundred Ninety Five Only
	Total					445225.05	
BIDDERS QUOTING AREA							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail				445225.05			
" This is a Electronic Submission No Need of Signature"							