

COCHIN PORT AUTHORITY

www.tenderwizard.com/CPT

Quotation No:T6/T-2064/2025-C Date: 15/10/2025

Name of Wok:“Replacement of Fender & fender accessories at various berths of Cochin Port Authority”

SCHEDULE- A- SCHEDULE OF QUANTITIES OF WORK

Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
A	Part A - Ernakulam Wharf						
1	Supplying and fixing Cell Type Rubber Fender 1250H at the specified location (Chainage 175 & 512) along with whole accessories and fixtueres such as SS bolts, nuts, washers, Anchor Bolts, Frontal Frame (1750mm x 2500mm), frontal pad, u-hooks, tension and weight chains etc. including cost of all materials, labour, loading/ unloading with necessary labour/machinery etc. complete as per detailed specifications and directions of Engineer-in-charge.	2.00	Each	8,10,000.00	Rupees Eight Lakh Ten Thousand Only	16,20,000.00	Rupees Sixteen Lakh Twenty Thousand Only
2	Taking out the 1250 H cell fender's frontal frame (1750mm x 2500 mm approximate size), chains and U clamps etc and stacking (At Chainages-390,574 & 636) including cost of all labour, tools, equipments etc. complete as per direction of the Engineer-in-charge.	3.00	Each	45,000.00	Rupees Forty Five Thousand Only	1,35,000.00	Rupees One Lakh Thirty Five Thousand Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
3	Supplying and fixing new 1250 H cell fender's frontal frame (1750 x 2500 mm approximate size), chains and U clamps etc. (At Chainages-390,574 & 636) including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of the Engineer-in-charge.	3.00	Each	6,00,000.00	Rupees Six Lakh Only	18,00,000.00	Rupees Eighteen Lakh Only
	Total Part - A					35,55,000.00	
B	Part B - Mattancherry Wharf						
1	Dismantling & removing existing damaged Cell Type Rubber Fender 800H along with all accessories and fixtures such as frontal frame, etc. without damaging the structures and stacking (At chainage 212, 333, & 580) including cost of all labour, tools, equipments etc. complete as per the directions of Engineer-in-charge.	3.00	Each	55,000.00	Rupees Fifty Five Thousand Only	1,65,000.00	Rupees One Lakh Sixty Five Thousand Only
2	Supplying and fixing Cell Type Rubber Fender 800H at the specified location (Chainage 212, 333 & 580) along with whole accessories and fixtures such as SS bolts, nuts, washers, Anchor Bolts, Frontal Frame (1300mm x 2300mm), frontal pad, u-hooks, tension and weight chains etc. including cost of all materials, labour, loading/ unloading with necessary labour/machinery etc. complete as per detailed specifications and directions of Engineer-in-charge.	3.00	Each	6,00,000.00	Rupees Six Lakh Only	18,00,000.00	Rupees Eighteen Lakh Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
3	Taking out the frontal frame and supply and fixing 30 mm thick UHMWPE rubbing piece (pad) over the existing Frontal Frame 1250 x 1250 mm of the 800 H cell fender with SS bolts and washers etc. and refitting the frontal frame including cleaning and epoxy painting (At Chainages - 466 & 604) including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of the Engineer-in-Charge.	2.00	Each	1,50,000.00	Rupees One Lakh Fifty Thousand Only	3,00,000.00	Rupees Three Lakh Only
	Total Part - B					22,65,000.00	
C	Part C - BTP Berth						
1	Dismantling & removing existing damaged Cell Type Rubber Fender 1150H along with all accessories such as frontal frame, etc. without damaging the structures and stacking at Mattancherry Wharf (At chainage 108, 236, 381 & 399) including cost of all labour, tools, equipments etc. complete as per the directions of Engineer-in-charge.	4.00	Each	55,000.00	Rupees Fifty Five Thousand Only	2,20,000.00	Rupees Two Lakh Twenty Thousand Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
2	Supplying and fixing Cell Type Rubber Fender 1150H at the specified location (Chainage 108, 236, 381 & 399) along with whole accessories and fixtures such as SS bolts, nuts, washers, Anchor Bolts, Frontal Frame (1750mm x 3000mm), frontal pad, u-hooks, tension and weight chains etc. including cost of all materials, labour, loading/ unloading with necessary labour/machinery etc. complete as per detailed specifications and directions of Engineer-in-charge.	4.00	Each	8,00,000.00	Rupees Eight Lakh Only	32,00,000.00	Rupees Thirty Two Lakh Only
	Total Part - C					34,20,000.00	
	Total Amount (Rs.) (Part A + Part B + Part C)					92,40,000.00	Rupees Ninety Two Lakh Forty Thousand Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
BIDDERS QUOTING AREA							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail			92,40,000.00			
" This is an Electronic Submission. No Need of Signature"							